

ACO Drain

Fairfax County Fire & Rescue - Herndon Station Herndon, VA



PROJECT PORTFOLIO

Product:

FG200, Ductile Iron Slotted grates

Contractor:

GC - Biscayne Contractors



Fairfax County Fire and Rescue Department is the largest fire department in the Commonwealth of Virginia.

This project consisted of 105 feet of FG200 and ductile iron slotted Load Class E grates inside the fire station.

FG200 is a 8" (200 mm) wide fiberglass system with choice of steel slotted Class C or ductile iron Class E grates. Grates are bolted into the steel frame with 2 bolts per 18" grate.